

GENERAL SPECIFICATION G2.7

Working in Existing Installations

CONTENTS

G2.7 Work Involving Existing Installations1

G2.7 WORK INVOLVING EXISTING INSTALLATIONS

- (a) For work involving existing equipment and plant, including work completed by the Contractor or other contractors on the Site, and connections to existing utilities, the Contractor shall have included in his rates and prices the additional time and cost which may be required to obtain further information or clarification from the manufacturer including the Board and relevant agencies or to trace out the existing infrastructure and/or completed works should the Contractor deem the information provided by the Board to be insufficient. This clause shall take precedence over other clauses involving documents of existing equipment or plant such that Contractor shall not hold the Board or S.O. responsible for any inaccurate or inadequate information on existing equipment and the Contractor shall not be entitled to any extension of time or cost reimbursement.
- (b) In the event of any discrepancies between actual installation configurations and those described in the Drawings, the Contractor shall notify the S.O. and shall use the actual installation configurations in their design according to the contract requirements.
- (c) Where work is to be carried out in any existing installation, including work completed by the Contractor or other contractors on the Site, the Contractor shall take all precautions necessary to ensure that all existing facilities and/or completed work required for the operation of the Works are not damaged or interfered with in any way.
- (d) The Contractor shall provide design information and as built information of completed/ installed works expeditiously to the S.O.. This information shall be provided to the other contractors working near the works.
- (e) There are several existing services leading into, out of, passing through the Site. Where necessary for the permanent works or site enabling works, the Contractor shall be responsible for carrying out detailed services detection and trial trenches to identify the exact location of these services, establish coordinates using a GPS unit, develop and maintain updated existing services drawings at Site, protect the existing services during the Contract period and allow for crossings of existing or new services through the Site. This includes temporary services required by the other contractors to serve their work areas.
- (f) Protection Against Damage.
- (g) The Contractor shall take all necessary precautions to avoid causing any unwarranted damage to roads, lands, properties, trees and other features and, during the currency of the Contract, shall deal promptly with any complaints by owners or occupiers.
- (h) Where any portion of the Works is close to, across, or under any existing apparatus of existing utilities or other parties, the Contractor shall work around, under or adjacent to all services in a manner designed to avoid damage, leakage or danger, and to ensure uninterrupted operation.
- (i) Should any leakage or damage be discovered, the Contractor shall at once notify the S.O. and the Statutory Authority concerned, and the Contractor shall afford every facility for the repair or replacement of the apparatus affected.

- (j) The Contractor shall be responsible for the preservation of all public and private properties, and shall use every precaution necessary to prevent damage thereto. If any direct or indirect damage is done to public or private properties by or on account of any act, omission, neglect or misconduct in the execution of the work on the part of the Contractor, such property shall be restored by the Contractor at his own expense to a condition similar or equal to that existing before the damage was done or he shall make good the damage in other manner acceptable to the S.O..
- (k) All repair works shall be done and completed within reasonable periods to the entire satisfaction of the S.O.. The Contractor shall submit his proposal for the remedial works to the S.O. for approval prior to commencement of such works. In addition, the Contractor shall bear all direct and consequential damages and losses arising from the execution of the works.
- (l) Prior to commencement of works, the Contractor shall inspect all adjacent properties for any existing cracks or damages observed.
- (m) It shall be the sole responsibility of the Contractor to record and submit to the S.O. all levels, photographs of visible damages as well as signs and indications thereof on all those existing structures likely to be affected by the excavations or piling works. All expenses incurred shall be deemed to be included in his rates and no additional payment will be made to the Contractor on any aspect to this requirement.
- (n) The Contractor shall not commence work until all necessary and desirable information on the conditions of existing structures have been collected, properly recorded and submitted to the S.O. and approval obtained to commence work.
- (o) The Contractor shall on the S.O.'s instruction repair all damages to existing properties when any damage, however minor, is detected after commencement of work.

END OF SECTION