

GENERAL SPECIFICATION G2.8

Management of Road Traffic

CONTENTS

G2.8	Management of Road Traffic	1
G2.8.1	Road Traffic Act, Chapter 276	1
G2.8.2	Overview - Traffic Management	1
G2.8.3	Road Opening Permits	1
G2.8.4	Closing of Existing Roads.....	1

G2.8 MANAGEMENT OF ROAD TRAFFIC

G2.8.1 Road Traffic Act, Chapter 276

- (a) The Contractor's attention is drawn to the Road Traffic Act, Chapter 276 (including all amendments thereafter in use) regarding the regulation of road traffic and the use of vehicles in Singapore.

G2.8.2 Overview - Traffic Management

- (a) The Contractor shall ensure that the flow of traffic on the existing roads and access is uninterrupted during the Contract Period, when traffic will be required to flow on existing roads and on temporary roads in the Site segregated as far as possible from areas where work is in progress. The Contractor shall provide signalling equipment as necessary to control the traffic to the satisfaction of the S.O. and the appropriate authorities. In the planning and execution of any temporary or permanent Works which may affect the traffic flow and/or access and egress for the Site, the Contractor shall co-operate closely with the S.O..
- (b) The Contractor shall implement traffic management procedures approved by the S.O. and provide specialist traffic supervisors for this purpose.

G2.8.3 Road Opening Permits

- (a) The Contractor is required to have a valid road opening permit, approved by LTA and other agencies. The road opening permit shall be valid during the Contract period.
- (b) The Contractor shall engage a full-time supervisor on site to supervise the road opening, signing arrangement, reinstatement works and to receive directions from LTA. The supervisor shall possess a certificate in Pavement Construction and Maintenance Course issued by the Building and Construction Authority (BCA).

G2.8.4 Closing of Existing Roads

- (a) In the event that closing of any existing roads to traffic is unavoidable in carrying out the Works, the Contractor shall provide temporary roads or other arrangements acceptable to LTA and S.O. to maintain the traffic flow. The Contractor's rates shall be deemed to include any such arrangement and all necessary submission for LTA's approval.

END OF SECTION