

GENERAL SPECIFICATION G2.10

Temporary Works

CONTENTS

G2.10	Temporary Works.....	1
G2.10.1	Temporary Access Ways	1
G2.10.2	Earth Retaining or Stabilising Systems (ERSS) and Other Temporary Structures	1
G2.10.3	Temporary Site Buildings	2
G2.10.4	Workers Quarters Not Allowed On-Site.....	2
G2.10.5	Project Signboard.....	2
G2.10.6	Protective Hoarding.....	2

G2.10 TEMPORARY WORKS

G2.10.1 Temporary Access Ways

- (a) The Contractor shall provide and maintain in safe working condition throughout the duration of the Contract all necessary temporary road crossings over drains and/or channels etc. to allow proper access to the Site. On practical completion, he shall clear them away and make good all works disturbed to the satisfaction of the S.O. and any agencies concerned or pay charges for such making good as may be deemed necessary by the agencies.
- (b) All temporary site accesses shall be formed by 200 mm thick reinforced concrete non-suspended slab on well-compacted hardcore blended with sand and well compacted subgrade.
- (c) Accesses shall be properly graded with proper site drainage in accordance to the approved Erosion Control Management Plan. The Contractor shall maintain all accesses and remove silt and earth deposits regularly as a preventive measure for erosion control.
- (d) The Contractor shall note that the Works may affect some existing public thoroughfares during the construction period. When required, the Contractor shall provide temporary crossings and accesses in lieu of the affected areas and accesses if any at his own cost and to the satisfaction of the S.O. and all relevant authorities. Temporary crossings and accesses shall be designed by a Professional Engineer (registered in Singapore) engaged by the Contractor. The Contractor shall submit the design to the S.O. and all relevant authorities, for approval prior to the commencement of works to provide these temporary crossings and accesses.
- (e) For construction access routes which cut across public footpaths and cycling tracks, the Contractor shall deploy full-time traffic marshals to ensure the safety of park users and prevent unauthorized access into the construction site.
- (f) The Contractor shall be deemed to have allowed for these provisions in his rates and no claim for payment of extra moneys associated with providing such will be entertained by the Board.

G2.10.2 Earth Retaining or Stabilising Systems (ERSS) and Other Temporary Structures

- (a) The Contractor shall submit to the S.O. and BCA drawings and details of all ERSS or other temporary structures he intends to construct. The S.O. may require modifications to be made if he considers the proposal to be insufficient and the Contractor shall give effect to such modifications at his own cost but shall not be relieved of his responsibility for the sufficiency thereof. The Contractor shall engage a Professional Engineer (including PE (Geo) where necessary as required by the S.O. and / or Building Control Acts and Regulations pertaining to Geotechnical Building Works) as the Qualified Person(s) to design [QP (D)] the temporary works, supervise its construction [QP(S)] and certify the temporary works fit for occupation, use and operation. All costs for the engagement of site supervision personnel to carry out site supervision, as required by the relevant BCA Building Control Acts and Regulations, are deemed to be included in the Contractor's cost and scope.

G2.10.3 Temporary Site Buildings

- (a) Temporary site buildings shall only be erected in locations approved by the S.O. and the form of construction shall be subject to the S.O.'s approval. All temporary buildings must be demolished and removed from Site after the completion of the Works subject to the S.O.'s approval.

G2.10.4 Workers Quarters Not Allowed On-Site

- (a) The Contractor shall neither construct buildings on the site for providing lodging and accommodation for workers nor permit his workers to live on the site.

G2.10.5 Project Signboard

- (a) The Contractor shall provide and maintain on site all project signboards including all necessary metal framing and stand, foundation, paintings and description of the project to the approval of the S.O.. The exact locations of the signboards shall be determined on site and subject to the S.O.'s approval. The general dimensions and layout of the signboard are as stated in the drawing. The signboard shall bear the name and logo of the project, the Board, Superintending Officer (S.O.), Contractor and other information as provided by the S.O.. Drawings and design calculation of the signboard, together with PE endorsement is to be submitted to the S.O. for approval before fabrication and installing on site. The signboard shall be dismantled/cleared away whole from site after the completion of the Contract subject to the S.O.'s approval.

G2.10.6 Protective Hoarding

- (a) The Contractor shall provide and erect to the satisfaction of LTA, the Board and S.O., all necessary protective screens, hoarding, shoring etc. that may be required, of a sufficiently substantial nature to prevent damage, nuisance or disturbance by debris or dust to adjoining properties, public roadways or persons or traffic passing nearby.
- (b) Unless otherwise specified, the protective hoarding to the whole frontage, sides and back of the site shall be of an approved type. All hoardings and footings shall be designed by a Professional Engineer engaged by the Contractor. The design shall include colour scheme and graphical designs / patterns to be painted on the hoarding.
- (c) Adequate warning signs of design/s accepted by the S.O. shall be posted at conspicuous locations on the hoarding to alert the public of the construction in-progress. Attention shall be given to exits for heavy machinery and vehicles leaving the site. Collapsible gates or similar shall be provided at all site exit points to effectively close off the site. Collapsible gates shall be placed at crossing points where the construction access crosses pedestrian /cycling paths. The Contractor shall deploy full time traffic marshals during working hours to ensure the safety of park users. Gates shall be kept closed when not in use.

- (d) Hoarding shall be of such design and construction suitable for the works in-progress and allow for reuse over the different phases of construction. They shall be close-boarded and not pose an inconvenience or a danger to the public due to poor construction or maintenance. If any part of the hoarding becomes disjointed, derelict or unsightly, such defects shall be rectified by the Contractor at his own expense. All hoarding shall be inspected by the Contractor at regular intervals. An inspection report shall be given to the S.O. each month. The Contractor shall remove the hoarding on completion of the works or as directed by the S.O..
- (e) The Contractor shall allow for beautification of the hoarding along the roads where required. The Contractor shall allow for beautification of the hoarding including the supply of artwork, plants and softscape to enhance the aesthetics of the hoarding surfaces.

END OF SECTION