

GENERAL SPECIFICATION G2.13

Sanitation and Waste Management

CONTENTS

G2.13	Sanitation and Waste Management	1
G2.13.1	Overview	1
G2.13.2	Sanitation	1
G2.13.3	Proper Washing Facilities.....	1
G2.13.4	Waste Management	2
G2.13.5	Construction Waste Disposal and Recycling Records	2
G2.13.6	Cleaning Up Periodically	2

G2.13 SANITATION AND WASTE MANAGEMENT

G2.13.1 Overview

- (a) The Contractor shall maintain the Site and all working areas in a hygienic condition and in all matters of health and sanitation shall comply with the requirements of the Board, the S.O. and the relevant Authorities.

G2.13.2 Sanitation

- (a) The Contractor shall be responsible for providing his own sanitation facilities for purposes of working at the Site. All sanitary appliances shall discharge to the temporary sewer system at the designated connection point as shown on the Drawings.
- (b) If the temporary sewer system is not available for any reason, the Contractor shall provide chemical type toilets and shall be emptied regularly by vacuum tanker until the temporary sewage system becomes available.
- (c) The Contractor shall ensure that his employees (and those of his subcontractors) only use the toilet facilities provided by the Contractor as part of his Site establishment. Any person found urinating or defecating elsewhere on the Site shall be removed from the Site immediately, and shall not be re-employed on the Site.
- (d) Where portable toilets are provided for workers remote from the Contractor's Site offices, the Contractor shall ensure that such facilities are adequately designed and sized, well maintained and in good condition at all times. Where connections to sewers are not available or feasible, it shall be the responsibility of the Contractor to ensure provisions are in place to facilitate the disposal of the sanitary waste by tanker trucks at least twice a week from the Site.
- (e) Application showing the proposed waste disposal facilities is to be submitted to the Water Reclamation Network (WRN) Department for approval before commencement of work.
- (f) The Contractor shall allow for maintenance of sanitary facilities during the Contract Period.
- (g) The Contractor shall allow for cleaners, conservancy charges and other associated charges necessary to keep all facilities in a sanitary condition.
- (h) On completion of the Works, when directed by the S.O., the Contractor shall decommission the temporary sewage system and remove temporary connections to the public sewers and carefully reinstate all facilities disturbed to the satisfaction of the S.O..

G2.13.3 Proper Washing Facilities

- (a) The Contractor shall provide in his staging area modern washing facilities, including proper hand basins and shower facilities.

G2.13.4 Waste Management

- (a) The Contractor shall provide for the removal and legal disposal off the Site of all rubbish and solid waste from his site facilities, Contractor's working areas and Common Areas, with collections being made at least daily. The Contractor shall coordinate his disposal with other TWRP contractors to minimize disposal truck traffic at the Site.
- (b) The Contractor shall make provision for the discharge or disposal from the Works and Temporary Works of all water and waste products howsoever arising and the methods of disposal shall be to the satisfaction of the S.O. and of any Authority or person having an interest in any land or watercourse over or in which water and waste products may be so discharged. The requirements of this Clause shall not limit any of the Contractor's obligations or liabilities, under the Conditions of Contract.

G2.13.5 Construction Waste Disposal and Recycling Records

- (a) The Contractor shall keep a log book on the record of waste materials from the demolition and earthworks on site.
- (b) The Contractor shall note it is necessary to assist the S.O. in the compilation of documentation on waste material disposal / recycling.

G2.13.6 Cleaning Up Periodically

- (a) All rubbish shall be cleared from the Site from time to time. The Contractor shall provide purpose made bulk bins at locations approved by the S.O. and shall deposit the waste and debris into these bins and shall make necessary arrangements for ultimate disposal of these wastes and debris at approved dumping ground.

END OF SECTION