

- (b) SSG1 may be available to the Contractor (and Other contractors) as a temporary staging or storage area on an as-needed basis up to end 2023 subject to approval by the S.O.. There will be no TOL fees required from the Contractor for the use of SSG1, but there will be no guarantee that SSG1 will be available to the Contractor for the areas and/or time periods requested by the Contractor, as it is subject to S.O.'s approval. The Contractor shall be responsible for the following:
- (i) Obtaining all approvals for road openings and providing access into the site;
 - (ii) All site preparation and maintenance works, including but not limited to:
 - 1) levelling of ground to the desired platform levels, compaction (where required); and
 - 2) hoarding, lighting, drainage, erosion control, vector control, housekeeping, grass cutting and other facilities and activities needed to maintain health, safety, security and environment of its allocated area and staff working within the allocated area to the requirements of the prevailing laws and regulations and Specifications.
 - (iii) Traffic management and ensuring that adequate washing bay facilities are provided to ensure that vehicles are cleaned prior to entering public roads;
 - (iv) Any infrastructure required for any use of the area in compliance with requirements of authorities;
 - (v) Maintenance of common areas shared with Other contractors, including but not limited to levelling of ground, removal of debris and carrying out of vector control, grass cutting and housekeeping; and
 - (vi) Provision of utilities (water, power, sanitation) for their own usage, including all consultation with authorities, connection fees and usage charges, and subsequent removal and reinstatement.
- (c) The Contractor shall note that additional areas of land at various other locations in the Tuas South area, referred to as South Staging Ground 2 (SSG2), may be available for use as temporary staging or storage areas. The Contractor may coordinate with the S.O. to obtain the latest information on land location, area and availability upon commencement. These areas are under the authority of Jurong Town Council (JTC) and Singapore Land Authority (SLA). If the Contractor plans to use these areas, he shall provide to the S.O. at least six (6) months' notice of any intent to establish a temporary staging area within these areas. The S.O. reserves the right to allocate land within these areas for Other contractors. There will be no TOL fees required from the Contractor for the use of SSG2 but there will be no guarantee that SSG2 will be available to the Contractor for the areas and/or time periods requested by the Contractor, as it is subject to S.O.'s approval. All conditions pertaining to the usage of SSG1 will also apply to SSG2.

- (d) The Contractor shall submit its plan of use for any staging areas to the S.O. for approval. The Contractor shall note that the staging grounds will also be utilised and occupied by Other contractors. The Contractor shall carry out all coordination, interfacing with Other contractors and provide the resources to carry out appropriate maintenance of common areas shared with Other contractors. Common areas include but are not limited to common accesses and entrances. Maintenance of common areas may include the levelling of ground, removal of debris and carrying out of vector control, grass cutting and housekeeping along the common access road. After use, the Contractor shall restore any areas of the staging grounds used to the pre-use condition and shall return the area as required by the authorities. Pre-and post-condition surveys shall be completed by the Contractor in coordination with the S.O and submitted to the S.O for approval.
- (e) The Contractor shall note that should he require additional areas for his plant, equipment and materials other than at the Tuas WRP area and SSG1/SSG2 areas, he shall be entirely responsible for making the necessary arrangements for hoarding, protection, maintenance, access, etc. subject to the approval of the S.O.. TOLs, rental charges and all costs arising thereof shall be borne by the Contractor. The Contractor shall reinstate the lands affected to the satisfaction of the S.O. on completion of the Works.

P2.4.4 Reinstatement of Working Areas and Staging Areas at Site

- (a) The Contractor shall reinstate the staging areas and any temporary working areas allocated to the Contractor as soon as possible after all work in those areas have been completed to keep the period of occupation to a minimum. The Contractor shall return the staging and temporary working areas to the S.O. in the condition received upon completion of its use of the staging area. The reinstatement shall include removal of all surface and subsurface facilities and infrastructure installed, clean-up of any waste disposed, removal of vegetation, levelling and compacting of ground to elevation of +5m SHD.

P2.4.5 Washing Facilities

- (a) The Contractor shall note that all roads within the Site shall be regarded as public roads with respect to the level of cleanliness and upkeep.
- (b) The Contractor shall provide, operate and maintain washing bays or an equivalent washing service (subject to S.O. approval) to ensure all the Contractor's vehicles leaving the Site during the Contract period are clean and vehicles wheels are generally free from debris. Washing services shall be operated during all working hours.
- (c) The Contractor shall design the washing facility to handle the washing of all types and numbers of vehicles used by the Contractor. The vehicle washing facility shall be of adequate width and length such that it completes a full rotation of wheel washing on both sides of the vehicle. The vehicle washing point shall be located such that vehicle wheels are cleaned the moment it travels on public road and no overflowing of water from the washing point to the public road shall be allowed. The wheel washing facilities shall also have adequate drainage and appropriate measure to prevent standing water and breeding of mosquito.
- (d) The Contractor shall provide the required number of workers, supervisors, equipment and machinery, water supply, silt trap and filtration system for recycling of the water etc. in support of the washing facility operations as required.