

Appendix P12A – Sampling and Analysis

Facility Code	Facility Name	Process Unit	Fluid	Description	Location	Analysis Group 12	Frequency	Analyses
WST02	Sidestream Nitrogen Removal							
	202	Sidestream N Bioreactor						
		WST02-202-SP-DC-110	Dewatering Centrate	EQ Tank discharge to Sidestream SBR tanks	EQ Tank TNK-0101/0201 Discharge			
					Manual grab	AG-SN12	1 per week	Alkalinity; BOD5(T); COD(T); TSS; pH; NH3; TKN
	204	Sidestream N Wasting and Separation						
		WST02-204-SP-DC-11	Dewatering Centrate	Discharge Wetwell discharge to ILM Grit Tank Effluent Channel	Discharge Transfer Pumps Discharge			
					Manual grab	AG-SN12	1 per week	Alkalinity; BOD5(T); COD(T); TSS; pH; NH3; TKN
	200	SIDESTREAM TREATMENT						
		WST02-200-SP-DC-11	Dewatering Centrate	DC Wetwell discharge to Sidestream EQ tanks	Inlet to EQ tank			
					Autosampler	AG-SN12	1 per week	Alkalinity; BOD5(T); COD(T); TSS; pH; NH3; TKN